



# Pion Collection

What we have learned from  
CNGS Horn realisation at LAL.

Project Leader: J.E C  
Responsible Engineer : J.L Borne  
+ 1,5 Engineers  
+ 2 Draftsmen  
+ 3 Technicians


Present LAL FTE team

# Introduction/Management



- The Horn/Reflector and their equipments (FCS, Strip-lines, cooling) was "in kind" contributions of the IN2P3 institute (delegate to LAL).
- From 2000 to end of 2003: two engineers at LAL (a senior and a young) were in charge of the conception with a know-how transfer from CERN expertise (namely S. Rangod & J.M Maugain).
- End of 2003 :
  - The senior engineer has left the laboratory for personal conveniences; while the young engineer was on sick-leave;
  - The LAL director asked me to lead the team. I was in charge of the OPERA-LAL team and we had finished with success the design and production of the front-end chip of the Target Tracker.

# Human resources





# Lesson 1: lack of resources...



The **human resources** were largely **insufficient**. That is to say, it should have been at least **2 times more**.

- 1 **Project Leader** relationship with CERN
- 1 **Engineer supervisor** (senior)
- 1 Team for **computation** (1 engineer + 1 assistant): thermal and mechanical stresses
- 1 Team for the **Inner Cond** and **O. Cond.** (1 engineer + 1 draftman + physicists): link with the physicists
- 1 Team for the **Electrical part** (3 engineers + 3 draftmen) : Stripline, Fast Coupling, Horn connexion (surface)
- 1 Team for the **Water Cooling** (3 engineers + 3 draftmen): Horn In and Out, Fast water coupling, Radioactive Water deionisation
- 1 Team for the **Horn support** and positioning (1 engineer + 1 draftman)
- 1 Team for **general drawing** (2 draftmen)
- 1 Team for **the control and tests**
- 1 Team for **mounting**: 5 technicians (1 experienced)


~ 10 engineers, 10 draftmen, 5 technicians      2÷3 years

# First Horn at CERN 7<sup>th</sup> April 04




BA7

The 1<sup>st</sup> Horn had **successfully** passed a 65,000 double nominal pulses test early may 04. The water cooling of the Inner and Outer Conductor has also been controlled Ok.



/BENE Wor (2  $10^7$  double-pulses in 5 years)  
presentation by J. Campagne

# Horn I.C Design & Studies



Length : 6.65 m


Min. thickness : 1.8 mm

Diameter : 30.8 à 136 mm

Made up of 9 conical parts and  
2 flanges :

1. in aluminum alloy 6082
2. electrons beam welded

# Thermal study



1.5 mm 'dynamic' thermal expansion enable by thin flange

2-3 November 2004



ECFA/BENE Workshop DESY  
Presentation by J.E Campagne

# Static study



There is a minimum of matter (improvement w.r.t "WANF" horn)

3 sets of cables reduce inner conductor deformation (bending)



Model for FEM analysis



# Dynamic study: fatigue strength



2mm deformation allowed for Magnetic volume increase

axi-symmetric vibration mode 1 (139 Hz)


1 Rigid flange

Pt 1 (mode 1; 1+2)

axi-symmetric vibration mode 2 (364 Hz)

Pt 3 (mode 1+2)


Pt 2 (mode 2; 1+2)  
 $\sigma_{ecr} = 54 \text{ MPa}$  (mode 2) [1]





# Horn I.C realisation




Metrology at CERN of the Horn I.C



conducteur interne SPT 12 C  
position du centre des sections / axe D1-D2



The cones have been machined at CERN




thick flange checking

2-3 Nov EB welding

ECFA/BENE Workshop DESY  
Presentation by J.E Campagne

# Measurements with the real Horn



Lesson 2: we can trust theoretical computations when the inputs are correct...



# Lesson 2: Material allowed/forbidden



Aluminium

Brass

Copper

Stainless Steel but limit the use (radioactive waste)

Nickel (only to coat the Inner Cond. à la NuMI)

Iron: except with epoxy painting for small pieces

Glass: it will turn to black colour but does not loss its property

ARCLEX composite in dry sector (eg. electrical connexion spacing)

Ceramic insulator: Ok

Plastic: NO

Grease: NO

■ Ok ■ NO

It is a nightmare: verify everything and the cost increase in general...

# Realisation problems...



We had to face major problems :

- a) **Non conformity** of the cabling system which able to align the Horn Inner Conductor Cured by LAL
- b) **Very bad quality of the electrical surface** machined by **SIMIC** company 3 FT LAL technicians during 2 months
- c) **Welding** quality questionable for some pieces Checked with LAL expertise


# Horn cabling system



Non conformity between O.Cond. And I. Cond.



# Electrical surfaces (I)



Hand polishing at LAL  
during 2 months by  
3 FT technicians







# Electrical surfaces (II)



Lesson 3: electrical surfaces are crucial (150÷180)kA



# Mounting phases



Adjusted at final phase





Insertion of External Conductors around the Inner Conductor. Close the magnetic volume and put on the frame...




# Welding x-check



LAL Document : TSB/200312-1



Lesson 4: the welding is crucial for the electrical current



Cut a small piece for investigation (SEM)

Let the welding cordon visible, it does not matter and prove that the welding is well done...

# Lesson 5: "innovation does not mean always improvement..."



The "new" connexion system is elegant but rely on the machining precision (cumulative errors) and restrict a lot the flexibility necessary for the stripline connexion which was a guide line for the "old" system...




# Nuts & Bolts



- Bolt quality: A4
- Use smaller bolts to use properly the BINX nuts
- Use Grower washer spilt

Lesson 6: check the quality of the nuts & bolts and the torque this is crucial !

# Cooling System: principle




# Cooling System : mounting phases



IC + OC + flanges cooling



Decoupling mechanical vibrations of OC and Water System




Welding of the water cooling system to avoid leak.

# Cooling System : measurement at CERN BA7 with Horn 1 and minimal cooling



Test at BA7 with CERN cooling installation (may 04/Horn 1)



In: reference  $\left\{ \begin{array}{l} \text{Neck temperature : } +(13 \div 15) \text{ } ^\circ\text{C} \\ \text{Out temperature (} \sim \text{Outer Cond.): } +(4 \div 5) \text{ } ^\circ\text{C} \end{array} \right.$

Expected 1/3 more with Beam ON  
But primary water foreseen at  $\sim 14^\circ\text{C}$




# Water Collection problem



Collection of radioactive cooling water

The ARCLEX (mica + glass) composite is not safe enough  
And all the collection should be rebuild.




Lesson 8: follow recommendations given by experienced people...

# Horn : controls at LAL



Lesson 9: a reception by CERN should have been done at LAL.



Horn ready for tests:

- water test for leakage search;
- electrical decoupling test:
  - 2kV frame-Ext. Cond.
  - 1kV sprinklers - Ext. Cond.


# R.I.C : problems pointed out by CERN



25th Nov. 03, S. Rangod send a red light to LAL concerning the machining of the flanges (at least) that does not allow good and robust welding.

Lesson 10: the welding is crucial for life time of the object but also for the electrical current

Radial welds in the most stressed area, not accepted



CERN proposal for the design of the reflector inner conductor

S. Rangod

# R.I.C : new fabrication





2mm Al thick plates rolled and welded




# R.I.C : continued



Orbital  
&  
Longitudinal  
TIG welding



# Strip-lines : simple drawing and some realisations at CERN "mécano"




Lesson 11: this is a complicated object which requires a lot of attention (flexibility for the mounting...)

# Strip-lines: movable part to plug the FCS (conception by CERN)




Movable part to plug and unplug the F.C.S



S. Rangod/CERN/PH

S. Rangod


# Fast Coupling System



Lesson 12: this is a complicated object too and CERN had not ready-made solution from past experience. Link with Maintenance Local Staff.




# F.C.S : conception of modified version



# F.C.S : 1<sup>st</sup> realisation at LAL




at LAL



Use plates instead of cables from CERN past experiences.




Feb.-Mar. 04



M10 "La Clusienne" bolts very efficient



V/BENE  
intation



Tricky spacing with bolts and BINX nuts

# F.C.S : mounting at CERN BA7




Strip-line part: errors due to lack of prototype (lack of time too, stressed by the schedule)

- gravity !!!
- ARCLEX bars not coupled to Copper plates
- Spacing between ARCLEX and Copper plate too tight for the plug in.

Lesson 13: Drawing is absolutely not sufficient for this job



Horn part: geometry not mastered






# F.C.S : mounting at CERN BA7




With some difficulties, we have managed to work out and proceed to the Horn tests. And the connexion was validated (no heating).



Unscrew 5 nuts

In operations the unplug/plug of the FCS should be done in few minutes.

CERN "mécano" strip-line in BA7






Folding can be precise enough



# F.C.S : new prototype at LAL



We are now engaged in a full scale prototype test bench at LAL




## Strip-line "simulation"

Test the ARCLX bar fixing, the spacing operation as well as the F.C.S plug in.

## Horn "simulation"

This should answer to: How to design a mounting tool and a mounting scenario to guaranty the geometry ?

# Geometrical positioning




Align IC w.r.t TH (cable tensioning)  
Align TH w.r.t Target Area frame

# Adjustable feet: 1<sup>st</sup> Prototype



22<sup>th</sup> June 04



Due to an interaction with the water cooling system **automatic plug in**, there will be a drastic redesign by CERN.


# Some costing

kCHF/k€



item	CERN original estimate (MoU in 2000)	LAL & CERN estimate (20 July 2004)
2 Horns + 1 Reflector	600 / 390	920 / 600
2 Cooling systems	100 / 65	181 / 118
3 Support Systems (originally motorized)	220 / 143	62 / 40
2 sets of striplines	170 / 111	268 / 174 <i>(incl. fast coupling)</i> <i>(incl. 20 kEuro tests)</i>
<b>Total</b>	<b>1090 / 709</b>	<b>1431 / 932</b>

May still increase...



**+30%**

It may turn out that it would have been wrong by a factor 2...







END

# Welding x-check





## Electronic microscope investigation at LAL



Internal welding structure is Ok

## Investigation with electronic microscope



Crack clearly visible starting from the surface. (only in this sample)

# New Protocol CERN-IN2P3-LAL



## LAL Responsibility:

- 1) Horn & Reflector Supports
- 2) Fast Coupling System
- 3) Reflector Inner Conductor
- 4) Reflector and Horn-2 assembly/modifications
- 5) Horn & Reflector + FCS + Supports drawings

IN2P3 contribution  
fixed to  
650k€ material  
+  
20 men.y


## CERN Responsibility:

- 1) Striplines
- 2) Water cooling systems
- 3) Horn-1 modifications and the specifications  
for Horn-2 & Reflectors

Estimate at  
~ 300k€  
+  
manpower

**Control & Reception at LAL by CERN & LAL**

# Laser tracker measurements



2-3 November 2004

ECFA/BENE Workshop DESY  
Presentation by J.E Campagne